



BREED VALLEY
MUNICIPALITY • MUNISIPALITEIT • UMASIPALA

'n Unieke en sorgsame Vallei van uitmuntende dienslewering, geleenthede en groei.
Intlambo ekhethekileyo enenkathalo, egqwesayo kuniko-zinkonzo, ivulela amathuba kwaye iphuhlise.
A unique and caring Valley of service excellence, opportunities and growth.

BID BV 953/2022

**UPGRADING OF GRAVEL ROADS AT ZWELETEMBA, WORCESTER
FOR THE PERIOD ENDING 30 JUNE 2024**

Bid closing date and time: NO CHANGE

ADDENDUM 2:

- Questions & Answers from Tenderers

20 April 2022

D. McTHOMAS
MUNICIPAL MANAGER

T2.2
BREEDE VALLEY MUNICIPALITY
BID BV 953/2022
UPGRADING OF GRAVEL ROADS AT ZWELETEMBA, WORCESTER
FOR THE PERIOD ENDING 30 JUNE 2024

T2.2 ADDENDUM 2: 20 APRIL 2022 – Questions & Answers

THE FOLLOWING QUESTIONS WERE RECEIVED FROM TENDERERS:

1. Typical drawing for v-drain:
We will issue specific drawings where it is deemed necessary once on site. This item is measured in m³ concrete.
2. Header row on all edges laid on 25MPa concrete. Is this the same Type S-A pavers.
The header row is of Type S-C Class 25MPa with thickness 60mm.
3. Joint Venture – Permission from Client.
Permission not required, however take note of Tender Data: Sub Clause F2.1.1
4. Item 13.1.2 Describes the pavers as Red Oxide colour, where as PS MJ 3.1.2 describes Grey colour
The Schedule of Quantities is correct, it should Red Oxide
5. Item: 1.3.5e) Cost of Labourer's Medical is a Prov Sum but there is no allowance for percentage mark-up
Please include Markup under 1.3.5 a) OHS Measures
6. Item 2.1.2 Take down existing fences, store and re-erect afterwards with the same material. What type of fence
This is a /km rate and all relevant fences are included. The contractor may verify what type it is on site if he chooses.
7. Item 10.14.1 states "Extra over item B11"
This should read: "Extra over item 10.13.1
8. Item 14.1.1 c) 300mm wide x 150mm thick 30MPa edge beam but the drawing indicates 300x200mm
Order of precedence of documents: Bill of Quantities take precedence.
9. Are there drawings for services
The survey data does not show all positions and depths of all services. Detail will be discussed on site.
10. Who is responsible to make arrangements with property owners' where fences are clearly constructed within the road reserve
The contractor with the assistance of the local authority structures.
11. Can the contractor's camp be located 'off site'
Yes
12. Would the RE need any offices
No
13. Take note of the Typical Drawings issued:
 - a. 2022-04-07 R900 Typical House Access
 - b. 2022-04-07 R901 Typical Speed Table
 - c. 2022-04-07 R902 Typical Field Inlet
 - d. 2022-04-13 R903 Water Pipe Thrust
 - e. 2022-04-13 R904 Pipe Bedding Details
 - f. 2022-04-13 R905 Fire Hydrant Details
 - g. 2022-04-13 R906 Erf House Connection Details
 - h. 2022-04-13 R907 Water Marker Post Details

- i. 2022-04-13 R908 Isolation valve details
- j. 2022-04-14 R909 Water erf connections

PLEASE NOTE: DETAIL OF THIS ADDENDUM MUST BE CAPTURED IN PAGE T2.2-27 OF THE TENDER DOCUMENT AS FOLLOWS:

SCHEDULE 3A : RECORD OF ADDENDA TO TENDER DOCUMENTS
--

We confirm that the following communications received from the Employer before the submission of this tender offer, amending the tender documents, have been taken into account in this tender offer:		
---	--	--

	Date	Title or Details
1.	11 April 2022	Typical Drawings & Corrections
2.	20 April	Questions received from Tenderers with Answers

I _____ from _____ hereby acknowledge that we have
(Name) (Tenderer)
received the above Addendum.

Signature

Date